

McKee and Associates
Architecture and Interior Design

Addendum

No. SIX Date: 01/05/11

Project: PHYSICAL EDUCATION FACILITIES
FOR MARBURY HIGH SCHOOL
FOR
THE AUTAUGA COUNTY BOARD OF EDUCATION
PRATTVILLE, ALABAMA

PROJECT NO. 10-166
BC # 2010979

A6.1 GENERAL

- A. The following changes and/or substitutions to the plans and specifications are hereby made a part of same and are incorporated in full force as part of the contract.
- B. Bidders shall acknowledge receipt of this Addendum in writing on his Proposal Form.
- C. Phasing Of Work: Phase 1 shall consist of all fences and gates, Visitors Dugouts, site utilities, netting, concrete sidewalks, Baseball and Softball Fields, Batting Cages, Bull Pens, site preparation and grading, electrical service, plumbing and mechanical systems, retaining walls. Phase 2 shall consist of all Home Dugout/Fieldhouses at both the Baseball and Softball Fields. All work in Phase 1 shall be completed by March 15, 2011, and all work in Phase 2 shall commence at the end of Baseball Season, June 1, 2011 and be completed by August 30, 2011. **All work of all the Separate Labor and Material Proposals shall be scheduled through the Owner**

A6.2 SPECIFICATIONS

- A. Refer to **Section 10500, Metal Lockers**, change as follows on Page 10500-1:

| <u>AREA</u> | <u>SIZE OF LOCKER</u> | <u># OF OPENINGS</u> |
|--------------|--|----------------------|
| Locker Room: | Single Tier Athletic Lockers 18" W x 15" D x 72" H | See Drawings |

- B. The following manufactures are hereby approved subject to the plans and specifications:

Section 10800, Toilet Accessories:
Columbia Accessories

A6.3 DRAWINGS

- A. Refer to **Sheet A3.0:**

Delete reference to Aluminum Benches in the Student Dressing Rooms. All benches in both Student Dressing Rooms shall be as specified in Section 10510, Locker Room Benches.

- B. Refer to **Sheet A2.0,** Chain Link Fencing Specifications, change as follows:

- 1) Fabric for fencing shall be as specified in Section 02831:

Fabric: 2 inch vinyl coated diamond mesh interwoven wire, 9 gage thick, top selvage twisted tight, bottom selvage knuckle end closed.

- 2) Provide rails as specified in Section 02831:

Top, Mid and Bottom Rail: 1-5/8 inch diameter, plain end, sleeve coupled with 0.111 inch wall thickness.

Delete the tension wire at the bottom of the fencing where a bottom rail is specified or indicated.

END OF ADDENDUM SIX